

**BOQ For Proposed Compound Wall & Civil Work @ CTS No. 1041 to 1045 Mate Wada , Satara - 415002**

SR. No.	ITEMS DESCRIPTION	Qty	Unit	Rate	Amount
1	Removing existing rabbit, other unwanted material before starting actual development etc. & carting away the material out side from shop at Contractor's responsibility.	Job	L.S.		
2	Demolition of brick masonry/RR/UCR masonry including plaster above/below ground level carefully and remove debris out of the campus at approved location by governing authority out side Wai Nagarparishad Limit including all legal permissions etc. complete.	1.47	m3		
3	Providing & laying RCC Pardi in M-30 grade concrete including scaffolding, plumb, casting etc. complete.	3.11	cum		
4	Providing mild steel bar to RCC pardi asd specified by engineer.	0.279	MT		
5	Providing & applying internal cement plaster / Single coat average 15 mm to 25 mm thick in cement mortar 1:4 (1part of cement 4 part of Washable Crush Sand , with neeru finish to concrete or brick surfaces, on walls & ceilings in all positions and at all levels including scaffolding & with chicken mesh at the junction of brick/block work & RCC members, item also include making groves, dhar. Core, band, including curing as directed & Up to the satisfaction of Engineer In Charge etc. complete.	33.45	m2		
6	<b>Departmental Labour</b>				
	a) Male Coolie	1.00	Per Day		
	b) Female Coolie	1.00	Per Day		
	c) BBM mason	1.00	Per Day		
	d) Plaster Mason	1.00	Per Day		
	e) Tiling Mistry	1.00	Per Day		
	f) Carpenter	1.00	Per Day		
	g) Welder	1.00	Per Day		
	h) Plumber	1.00	Per Day		
	i) Helper - Carp./ Tiling / welding / Plumbing Work	1.00	Per Day		
	j) Welding Machine	1.00	Per Day		
	k) Braker machine Rent	1.00	Per Day		
	l) cutter machine Rent	1.00	Per Day		
		<b>Total</b>			
		<b>Add GST 18%</b>			
		<b>Total Amount</b>			